

TOWN OF SEARSMONT, MAINE

ROAD SHIM AND OVERLAY PROJECT - BID SPECIFICATIONS

1. PROJECT DESCRIPTION

The Town of Searsmont is accepting sealed bids for the shim and overlay paving of an existing roadway.

Road Width: 18 feet (typical)

Road Length: 2,200 ft southerly from the town line

2,011 ft southerly from culvert just north of School Street

Location: Appleton Ridge Road

Surface Type: Existing asphalt pavement

2. SCOPE OF WORK

Contractor shall furnish all labor, materials, and equipment necessary.

Surface Preparation: Clean pavement, remove loose material, shim low areas. Remove rock from center road near mailbox #170

Shim Course: HMA per MaineDOT Section 401.

Tack Coat: Apply per Section 409.

Surface Overlay: 1.5-inch compacted HMA surface.

Shoulder Work: Blend edges and adjust shoulders, removing rocks as needed.

Traffic Control: Maintain safe passage per MUTCD standards.

3. MATERIALS

All materials shall meet MaineDOT Standard Specifications including Sections 401, 409, and 703.

4. CONSTRUCTION REQUIREMENTS

No paving on wet surfaces or below 40°F. Proper joint construction required.

5. QUALITY CONTROL

Contractor responsible for QC. Town may perform independent testing.

6. MEASUREMENT AND PAYMENT

Shim Course HMA (Ton)

Surface Course HMA (Ton)

Tack Coat (Gallon)

Traffic Control (Lump Sum)

Surface Prep (Lump Sum)

7. BID SUBMISSION

Submit bids by [Insert Date/Time] to Town Office, Searsmont, Maine.

8. CONTRACT TIME

Work completion by June 19, 2026

9. INSURANCE REQUIREMENTS

Contractor must provide proof of insurance.

10. GENERAL CONDITIONS

Town reserves right to reject any bids.

11. CONTACT INFORMATION

Proposals shall be submitted to:

Town of Searsmont

Address: 37 Main Street, South
PO Box 56
Searsmont, ME 04973

Email admin@searsmont.com

All proposals must be received by the due date listed above.